



Case History #107

North America's premier
waterproof vinyl flooring
systems. Since 1974.

Project:

Northwest Community College
Terrace, British Columbia

Date:

Spring 1992




Problem:

Ceramic tile floors in showers, sink and toilet areas were leaking into and through the ceilings below. The maintenance staff of the college had tried other methods of waterproofing the grout lines, but with no lasting success.

Duradek Solution:

DURADEK SUPREME (25 mil) Different Colours.

Duradek was glued with contact type adhesive directly over the ceramic tiles with no prep work whatsoever. The grout lines were very thin and did not telegraph through the vinyl. The perimeters of the toilet and change areas were secured with "L" trim used as a gum stop and sealed with urethane caulking. In the showers, the **Duradek** membrane was run up the walls 8 inches and lapped with a shower wall panel. The vinyl was "seated" into a urethane sealant around the existing shower drains.



Applicating Contractor:

DLN Contracting Ltd.
Terrace, British Columbia
(604) 635-5859 Fax: (604) 635-5855

Job Notes:

Six of these shower/change areas have been done to date. The success of solving this problem has led to other uses on campus such as ramps and stairs.

For more information about the complete Duradek product line call (604) 591-5594 or fax (604) 591-3100